



LIGHTNING ELECTRIC

RBELLO CORP

PO Box 216 Blauvelt, N.Y. 10913 • Phone: 845.365.2285

rob@lightningelectricny.com

PROPOSAL

Date: 4/10/2026

To: Valley Cottage Library

Job: 110 RT 303

Valley Cottage, NY 10989

Attn: Christy Blanchette

Quantity	Description
----------	-------------

Scope of Work

Supply & install Raychem Wintergard Wet Roof & Gutter De-icing System
Heat Trace system will cover all gutters and downspouts on building
Includes Wintergard cable, power connections, splice kits, downspout hanger brackets, roof clips and automatic snow/ice melt controls
We will install 1- 208V, 30A circuit, 1- 208V, 20A circuit and 1- 208V 15A circuit for heat trace system
We will run circuits from the existing panel on the rooftop to our three circuit locations
Supply & install Siemens circuit breakers for the above listed circuits
All circuits for heat trace will be run in conduit on the roof/inside attics in free air if possible, to the start of each heat trace run

Total For Above: \$ 44,300.00

Acceptance of Proposal- The above prices, specifications, and conditions are satisfactory and are hereby accepted. You are authorizing Lightning Electric to do the work as specified. During installation, if any unforeseen conditions arise and if any electrical equipment that is deemed unsafe or in need of replacement are found and is directly correlated with the completion of our work, repairs are not included in this contract. A written quote for the change order will be given to replace any of this equipment at the time of discovery.

**Customer
Signature**

Date:
